

Bruhath Bangalore Mahanagara Palike Dasarahalli Zone

Name of Work: Providing street name board at AGB layout, Babanna layout and Medarahalli in W.no.12 Shetty halli Sub division

Est .Cost Rs. 10.00 Lakhs

SI No	Description of Items	Unit	No	L	B	D	Qty	Rate	Amount
1	KSRRB 300-1. Earth work excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications MORTH chapter 3. Page No. 141 / Item No. 19.1/ PWD SR 2015-16								
	At main and cross roads	<i>cum</i>	115	0.6	0.6	0.80	33.12	83.16	2754.00
	Basic Rate		77.00						
	Area Weightage @ 8%		6.16						
	Total		83.16						
2	Lead for Disposal of Debris shall be payable at carriage rates by Mechanical means including loading and unloading. From 0.00 to 2.00 Km (Page No.133 of PWDSR 2015-16)								
		<i>cum</i>		Vide Item No. 1			33.12	78.97	2615.00
	Average weight of earth 1.28 tonne / kg for 2x1.28x2.00=5.12		5.12						
	Add loading and unloading charges Vide item no.17.1 P.no.133		68.00						
			73.12						
	Area Weightage @ 8%		5.85						
	Total		78.97						
3	KSRRB 4-1.3 : Providing and laying in position plain cement concrete of mix 1:3:6 with OPC cement @ 220 kgs with 40mm and down size graded granite metal coarse aggregates @ 0.892cum and fine aggregates @ 0.465 cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1,4.2. No. 12/ Item No. 4.2/ PWD SR 2015-16								
	for Sign Boards	<i>cum</i>	115	0.60	0.60	0.20	8.28		
							8.28	5236.92	43362.00
	Basic Rate		4849.00						
	Area Weightage @ 8%		387.92						
	Total		5236.92						
4	KSRRB- 4-1.5 : Providing and laying in position plain cement concrete of mix M20 with OPC cement @ 300 kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.64 cum and fine aggregates @ 0.43 cum with superplasticiser @ 3lts confirming to IS9103-1999 reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15cms, thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing complete as per specifications, specification. No. KBS 4.1,4.2, No. 12/ Item No. 4.5/ PWD SR 2015-16								
	for Sign Boards	<i>cum</i>	115	0.60	0.60	0.60	24.84		
							24.84	5991.84	148837.00
	Basic Rate		5548.00						
	Area Weightage @ 8%		443.84						
	Total		5991.84						

CERTIFICATE:

- Assistant Engineer
Ward 12

ನಂ. ೮೬/೧೦/೧೯/೦೪ / ೨೦೧೬-೧೭ : ೦೪/೧/೨೦೧೬
 10.00 Lakhs (Rupees Ten lakhs only)
 Executive Engineer
 Dasarahalli Division
 BBMP
 ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು
 ಬಿ.ಬಿ.ಎಂ.ಪಿ.ದಾಸರಹಳ್ಳಿ ವಿಭಾಗ
 ದಾಸರಹಳ್ಳಿ ಪಲಯ, ಬೆಂಗಳೂರು